

P.O. Box 1070, Woodridge N.Y. 12789 Phone: 845-434-7805 Fax: 845-434-0307

15 February 2021 Quotation 21.5482.1-RBH

Jennifer Hubbard Yonkers Public Schools One Larkin Center Yonkers, NY 10701

RE: Tank Replacement project

PS 16, 759 North Broadway, Yonkers, NY NYSDEC PBS #3-413364 & Spill # 2004978

Dear Ms. Hubbard,

Luzon Environmental Services (Luzon) is a specialty contractor with forty-five years' experience. References can be provided upon request. Thank you for this opportunity for Luzon to provide a proposal.

This is to follow up the failure of an underground fuel tank tightness test, the subsurface investigation, cleaning the tank and sampling around the tank for rock.

Luzon proposes to remove the existing tank, supply an install one new 8,000 gallon double wall fiberglass UST with: 1-1/2" supply and return lines, below grade spill container at the fill with an overfill prevention valve, electronic tank monitoring system with inventory and leak monitoring. Included is replacement of the pump set & the concrete and asphalt work as specified on the drawings.

This cost is for a complete project.

Costs:

| Fee Schedule Service / Equipment / Labor | Estimated | Unit Fee | Estimated |
|--------------------------------------------|-----------|--------------|--------------|
| | Quantity | | Cost |
| Pump Set replacement Labor | 1 | 4,821.00 | \$ 4,821.00 |
| Pump Set materials | 1 | \$ 15,894.70 | \$ 15,894.70 |
| Pump set allowance if piping in the boiler | 1 | \$ 2,000.00 | \$ 2,000.00 |
| room needs replacement | | | |
| Mobilization and tank removal | 1 | \$ 18,370.00 | \$ 18,370.00 |
| Prep for tank install | 1 | \$ 7,277.00 | \$ 7,277.00 |
| Set Tank & Backfill | 1 | \$ 14,111.00 | \$ 14,111.00 |
| Complete Backfill & Tank Top | 1 | \$ 9,631.00 | \$ 9,631.00 |
| Piping & Electrical | 1 | \$ 17,210.00 | \$ 17,210.00 |
| Testing & Cleanup | 1 | \$ 13,544.00 | \$ 13,544.00 |
| Materials-Tank, accessories, piping to and | 1 | \$ 61,373.00 | \$ 61,373.00 |
| from the tank, and electronics | | | |
| Stone | 200 tons | \$ 40.00 | \$ 8,000.00 |



P.O. Box 1070, Woodridge N.Y. 12789 Phone: 845-434-7805 Fax: 845-434-0307

| Total project | 1 | \$ 287,212.45 | \$ 287,212.45 |
|--------------------------------------------------------------|---|---------------|---------------|
| Invoice # 5022 | 1 | \$ 11,567.00 | \$ 11,567.00 |
| Invoice # 4874 | 1 | \$ 39,598.75 | \$ 39,598.75 |
| Work Completed and invoiced | | | |
| Project management | 1 | \$ 5,000.00 | \$ 5,000.00 |
| Tank closure site assessment including 5 samples @ \$ 275.00 | 1 | \$ 3,375.00 | \$ 3,375.00 |
| Markup on Peter Landi 20% | 1 | \$ 9,240.00 | \$ 9,240.00 |
| asphalt including \$ 4,900 allowance for 8" sdr pipe. | | Ş 40,200.00 | Ç 40,200.00 |
| Peter Landi Subcontractor concrete & | 1 | \$ 46,200.00 | \$ 46,200.00 |

Luzon provides the following cost proposal with the following assumptions:

- Dig Safe NY will be notified at least 3 days prior to start of project.
- Labor will be paid prevailing wages. Certified payrolls will be submitted.

Additional work or equipment will be quoted if needed.

Payment Terms: Payment is due net 60 days.

This proposal is valid for 30 days.

Respectfully submitted,

Robert B. Halprin President