



November 8, 2024
Mr. Al Delillo
Assistant Director Schools Facilities Management Dept.
Yonkers Public Schools
1 Larkin Plaza
Yonkers, NY 10701

Mr. Delillo:

Thank for this opportunity to quote on some you of your Bathroom Partition requirements which are available from us on Southern Westchester BOCES Bid 2023-24-C09, Item # O3, Global Partitions.

I have examined the Bathroom Partitions at your Vive School # 10 and find that you will require a total of 19 Bathroom Compartments and 7 Wall Hung Urinal Screens. For the sum of \$58,581.40 we hereby offer to supply and install the same complete.

This quotation is based on utilizing American Specialties HDPE Solid Polymer Partitions. With a textured finish to hide the effects of vandalism, it is the low maintenance material of choice as minor scratches can often be repaired. The High-Density Polyethylene (HDPE) panels are virtually impenetrable by water, odor, mildew and soap and most commercial cleaning agents will not damage the surface. Fire Code Compliance: NFPA 286 fire test criteria. **Specifications include Stainless Steel Continuous Brackets. Included will be the removal and disposal of the existing Ceiling Hung Bathroom Partitions.**

BOCES Breakdown:

3 Alcoves 66" to 72"w @ \$1,770.00 = \$5,310.00
1 Alcove 74" to 96"w = \$2,168.00
3 Model FS2's @ \$5,114.00 = \$15,342.00
1 Model FS4 = \$9,098.00
1 Model FS6 = \$12,950.00
3 Model 5082480 Urinal Screens @ \$348.00 = \$1,044.00
27 Model 8266010 Continuous Stainless-Steel Brackets @ \$260.00 = \$7,020.00
18 Model 8266020 Continuous Stainless-Steel Brackets @ \$260.00 = \$4,680.00
Total BOCES List Price = \$57,612.00
Minus BOCES Discount (5%) = \$2,880.60
Total Net BOCES Material = \$54,731.40
Plus Prevailing Wage Installation = \$3,850.00
Total Net Installed Price = \$58,581.40

Exclusions:

Removal of Threaded Rods which are not accessible
Removal of Support Structure above the existing ceilings
Repair of Sheet Rock or Tiles on walls or ceilings

Very truly yours,
Sal Barbera