



71 Marsh Rd East Rochester, NY 14445 585-586-7705 Fax 585-586-7706

Vehicle Purchase Proposal

Attention: Jackie

Yonkers Public Schools

375 Kneeland Ave Maintenance Dept
Yonkers NY 10704

Phone: 914-376-8383 Fax: 914-376-2668

Mobile: 914-844-2486 Rafael Sanchez Email: jpagliaroli@yonkerspublicschools.org

Final Order Date Yet To Be Determined
Quote# 34795

Onondaga Bid ONGOV-106-19 2024

Item Description	Code	Qty	Your Price	MSRP
2024 F-450 XL Reg Cab 4x4 DRW 169 WB 84 CA	F4H	1	\$ 49,764.00	\$ 63,800.00
Oxford White	Z1	1	\$ 0.00	\$ 0.00
7.3L 2V DEVCT NA PFI V8 Gas	99N	1	\$ 0.00	\$ 0.00
TorqShift Ten-Speed 10R140 with Neutral Idle Automatic with Selectable Drive Modes: Normal, Eco, Slippery Roads, Tow/Haul, Trail (4x2), Off-Road (4x4)	44G	1	\$ 0.00	\$ 0.00
Platform Running Boards (w/ Regular Cab)	18B	1	\$ 288.00	\$ 320.00
110V/400W Outlet	43C	1	\$ 157.50	\$ 175.00
Standard options for '24 – Power Equipment Group, Cruise, Brake controller, Sync4	650A	1	\$ 0.00	\$ 0.00
Dual Extra Heavy-Duty Alternator	67B	1	\$ 103.50	\$ 115.00
Suspension Package, Extra Heavy Service	67X	1	\$ 112.50	\$ 125.00
Exterior Back-up Chime	76C	1	\$ 157.50	\$ 175.00
Dual Batteries (68 Amp.) 43C or 47A or 47L	86M	1	\$ 0.00	\$ 0.00
Vinyl 40/20/40 Split Bench - (XL Only) (Regular Cab)	AS	1	\$ 0.00	\$ 0.00
LT225/70R19.5G BSW Traction (4) A/P (2)	TGM	1	\$ 171.00	\$ 190.00
Axle, Limited-Slip 4.88 Ratio (7.3L)	X8L	1	\$ 355.50	\$ 395.00
Tommy Gate Dump Through Liftgate Installed Model G2-92-2050 LD33 83" x 33" Load Area with 6" Taper Powder Coated Black Steel Construction 2000# Lifting Capacity Bolt On LED Light Kit Installed		1	\$ 7,910.00	\$ 11,300.00
Cab Rooftop Light Installed LED Amber Mini Bar Installed Clear Lens, Amber Flash Permanent Mounted to Cab Roof Wired to Factory Upfitter Switch or Dash Toggle		1	\$ 686.00	\$ 980.00
Rear Hitch Plate Installed 1/2" Formed Plate Welded and Gusseted to Truck Frame Customer's Choice of Hitch Coupler Installed (Customer Must Specify Size & Height) D Rings and Seven Way Electric Plug Installed Utilize Factory OEM Electronic Brake Control In Cab		1	\$ 1,736.00	\$ 2,480.00
Front and Rear Amber Strobe Lights Installed (4) Surface Mount Amber LED Strobes Installed Wired to Factory Upfitter Switch or Dash Toggle		1	\$ 1,190.00	\$ 1,700.00
10ga Smooth Steel Flooring ILO Wood Flooring		1	\$ 252.00	\$ 360.00
SR4016 Rugby Subframe and Hoist Assembly Double Acting, Electric Over Hydraulic Power Unit Power Up, Power Down Approximatley 10 Ton Lifting Capacity In Cab, Pendant Style Control Body Up Indicator Installed Back Up Alarm Installed		1	\$ 5,327.00	\$ 7,610.00
42" Drop In, Spring Loaded Rack Sections Slotted Steel, City Stake Rack Sections Side Sections Only		1	\$ 2,548.00	\$ 3,640.00
42" Drop In, Bolt On Bulkhead with Window		1	\$ 896.00	\$ 1,280.00
Delivery to Region 5 (Onondaga Bid 2014)		1	\$ 520.00	\$ 520.00
Rugby 12' HD Series Platform Body Fits 84" CA, Dual Rear Wheel, Straight Frame Chassis 12'4" Overall Length, 96" Overall Width 10 Gauge Steel Construction Throughout 6" Structural Channel Long Rails 8 Gauge Crossmembers on 16" Centers 3/8" x 2" Outside Banding Rail Down Sides and Rear 2" x 4" Exterior Stake Pockets (Front, Sides, Rear) Standard Marker Light Kit Pressure Treated Yellow Pine Floor, Tongue & Groove Chassis Light Adapter (Blunt Cut Harness if Not Available)		1	\$ 6,622.00	\$ 9,460.00
Standard Installation Includes Rear Rubber Flaps with Stainless Steel Antisails Fuel Fills as Needed ICC Underride as Necessary U Bolt Tie Downs and Shear Plates Reuse Chassis Mounted S/T/T Lights Conspicuity Tape Across Rear Only		1	\$ 0.00	\$ 0.00
	Total Price:		\$ 78,796.50	
Quantity on this Order: 1	Grand Total:		\$ 78,796.50	

To place an order please sign and date this proposal and return it to
Van Bortel Ford along with a valid Purchase Order, Voucher, or Letter of Intent. Thank You!

Accepted By: _____ Title _____ Date _____
Van Bortel Ford Inc (WBE) Federal ID 16-1609363 Salesperson: George Lunney Quote: 34795